NOTE:

THE LOCATION OF THE UTILITIES IS APPROXIMATE ONLY AND THE EXACT LOCATION SHALL BE DETERMINED BY CONSULTING THE MUNICIPAL AUTHORITIES AND UTILITY COMPANIES CONCERNED. THE CONTRACTOR SHALL PROVE THE LOCATION OF UTILITIES AND SHALL BE RESPONSIBLE FOR ADEQUATE PROTECTION FROM DAMAGE.

(2) Class 'B' bedding to be used throughout the sewer system

(3) Place 12" of granular 'A' material as trench topping at driveways, parking lots and laterals at road crossings, and on roads as shown.

(4) All surfaces - restore to original condition.

LEGEND

#16 [736.52] DENOTES BASEMENT ELEVATIONS ON EAST SIDE OF STREET.

[733.83] #13 DENOTES BASEMENT ELEVATIONS ON WEST SIDE OF STREET.

No.	Revision	Date	Initial

Approved

REGISTERED PROFESSIONAL ENGINEER G. K. STRACHAN PROVINCE OF ONTARIO

TOWN OF PELHAM
1973 SEWER EXTENSION

VALIANT STREET

STA. 0+00 TO STA. 7+50

Proctor & Redfern Limited
Consulting Engineers
Toronto St. Catharines

Scale Hor 1" = 40' Vert 1" = 10'
Date: NOV, 1973

Drawn By R.S.O.
Ckd. By
Field Book 8643
Drawing No. B-73388-P2
Rev. 0

TRANSLAR 20-6-72