SCHEDULE

" A "

to

BY-LAW # 613 (1980)

METES AND BOUNDS DESCRIPTION ENLARGEMENT OF PELHAM WATER AREA NO. 1

COMMENCING at a point on the centre line and on the northerly limit of Lot 13, Concession IX in the former Township of Pelham, the said point being the northwest corner of Registered Plan No. 17, now known as Plan 704;

THENCE southerly along the centre line of Lot 13, Concession IX a distance of 384.871 metres to a point which is measured 91.440 metres perpendicularly distant from the centre line of Canboro Road;

THENCE easterly along a ling which is parallel to and perpendicularly distant 91.440 metres from the centre line of Canboro Road a distance of 81.077 metres;

THENCE north 0° 05 feet west a distance of 137.696 metres;

THENCE north 83° 07 feet east a distance of 28,937 metres;

THENCE north o 0 05 feet west a distance of 212,659 metres, the said point being on the north limit of Lot 13, Concession IX;

THENCE south 89° 07 feet west along the north limit of Lot 13, Concession IX a distance of 102.084 metres;

TO THE SAID POINT OF COMMENCEMENT.

S C H E D U L E

" B "

to

BY-LAW #613 (1980)

WATERMAINS AND APPURTENANCES TO BE CONSTRUCTED AS FOLLOWS:

Street

From

To

Sunset Drive

Canboro Road Memorial Drive

SCHEDULE

" C "

to

BY-LAW #613 (1980)

ESTIMATED COST OF WORK

| Construction - | |
|---|----------|
| 497 lineal metres of 200 millimetre watermain | \$29,340 |
| at \$59.03 per lineal metre | |
| Construction to existing watermain | \$ 1,000 |
| 2 valves at \$500.00 each | \$ 1,000 |
| 4 hydrant sets at \$1,500.00 each | 6,000 |
| 20 services at \$250.00 each | 5,000 |
| Engineering | 8,000 |
| Contingencies | 2,660 |
| TOTAL ESTIMATED CONSTRUCTION COST | \$53,000 |