#### SCHEDULE

" A "

to

#### BY-LAW NO. 909 (1984)

COMMENCING at a point in the north boundary of Lot 13, Concession 9 in the former Township of Pelham, now in the Town of Pelham, distant 52.2m east of the northwest corner of the said lot, which point may be called the place of beginning:

THENCE south on a line drawn parallel to the west limit of the said lot a distance of 162.6m to a point;

THENCE east on a line drawn at right angles to the west limit of the said lot a distance of 15.9m to a point;

THENCE south along a line drawn parallel to the west limit of the said lot a distance of 108.5m to a point;

THENCE east on a line drawn at right angles to the west limit of the said lot a distance of 12m to a point;

THENCE south along a line drawn parallel to the west limit of the said lot a distance of 96.35m to a point;

THENCE west along a line drawn at right angles to the said west limit of the said lot a distance of 161.3m to a point;

THENCE north along a line drawn parallel to the west limit of the said lot a distance of 366m to a point;

THENCE east along the north limit of the said lot and its westerly extension a distance of 188.4m to the place of beginning.

## SCHEDULE

"В"

to

BY-LAW NO. 909 (1984)

## WATERMAINS AND APPURTENANCES TO BE CONSTRUCTED AS FOLLOWS:

Street

From

To

Balfour Street

a point approximately 170 metres north of

Memorial Drive

Canboro Road

# SCHEDULE

" C "

to

BY-LAW NO. 909 (1984)

## Estimated Cost of Work

# CONSTRUCTION

150mm watermain - 416 metres	
at \$52.26 per metre	\$21,744.00
Valves and connection to main	275.00
Hydrants	4,500.00
10 services at \$375.00 each	3,750.00
Restoration	800.00
Engineering	5,700.00
Contingencies	2,000.00
TOTAL ESTIMATED CONSTRUCTION COST	\$38,769.00